















Based on the "WHO Operational Planning Guidelines to Support Country Preparedness and Response to COVID-19", the project seeks to limit the impact of COVID-19 by reinforcing national public health capabilities and infrastructures, particularly of least developed countries, who dramatically lack the material and human resources to address the public health emergency.

Three major packages – combined or single solutions



RAPID RESPONSE TEAMS (RRT'S) FOR SCREENING OF THE GENERAL POPULATION

- RRT's are equipped with emergency kits, containing a Solarworx Solego battery based mobile
 solar home system including a solar panel, which can power the included non-contact infrared
 (IR) thermometer, UV sterilization light, stethoscope, oxygen density measurement, pulse
 measurement device, doppler, ventilator, security light, USB phone charging kit and a hand free
 headlamp.
- Training to personnel of RRT's on investigation protocols and clustering.
- Suspected COVID-19 cases will be referred to mobile laboratories for testing.

MOBILE, SOLAR POWERED LABORATORIES TO TEST SUSPECTED COVID-19 CASES AND DIFFERENT PATHOGENS



- Mobile labs: Based on Solarkiosk solar power integrated infrastructure, the E-HUBB. Solar power
 is being inverted into usable AC energy and stored into long life LiFePO₄ batteries for night-time
 usage with the BOS AG hybrid solar inverter & battery charging systems. Hot water for hygiene will
 be procured by PV powered Nexol boilers.
- The airconditioned modern lab contains state of the art laboratory equipment from Siemens
 Healthineers, enabling the users to establish with 100% certainty if a patient has been infected
 with the COVID-19 virus.
- Training to personnel of mobile laboratories on standard procedures.
- Confirmed COVID-19 cases will be referred to available health facilities.

MOBILE, SOLAR POWERED CLINICS TO TREAT CONFIRMED COVID-19 PATIENTS WITH A CAPACITY OF 90 BEDS



- Mobile clinics will take the form of tent structures. The energy is provided by a BOS AG hybrid energy system consisting of a solar power system that works with a required alternative source of energy such as grid electricity or a diesel generator. The solar power is being inverted into usable AC energy and stored into a battery bank for night-time usage. When there is not enough solar energy available, the batteries can be recharged with grid electricity or electricity from a diesel generator. The electricity is being used to power life saving equipment, such as ventilators, patient monitoring, X-Ray and other important medical devices to treat patients. Hot water for hygiene will be procured by PV powered Nexol boilers.
- The clinic will be divided in 3 levels; Intensive Care, 10 beds (5 for females, 5 for males).
 Patients with severe symptoms but no need for intensive care, 40 beds (20 for females, 20 for males).
 Patients with milder symptoms 40 beds (20 for females, 20 for males).
- Training to personnel of mobile clinics on Infection Prevention and Control (IPC) protocols.
- Training to medical / ambulatory teams on management of severe acute respiratory infections and COVID-19-specific protocols.

Scope of delivery - lab and clinic

Turnkey mobile solar powered LABORATORY		
Construction	E-HUBB container including PV equipment BOS Smart Energy Storage System Nexol water boiler	
Lab equipment	 Equipment Lab e.g. Stratus® CS 200 Acute Care™ Analyzer, ADVIA 560 hematology system, DIMENSION EXL 200, RapidPoint 500e blood gaz analyser, PCR Workstation Warranty on all equipment 	
Installation	Installation of solar system Commissioning of system and equipment	

Mobile solar powered CLINIC		
Construction	 Fully Equipped ICU tent including PV equipment 6 x easy-to-mount, fully equipped tents with a capacity of 90 beds BOS Smart Energy Storage System Nexol water boiler 	
Medical equipment	 Equipment clinic, e.g. Patient Monitor, Portable ultrasound, Breathing machine, Radiography portable, 12 leads ECG electrocardiogram Warranty on all equipment 	
Installation	Installation of solar system Commissioning of system and equipment	

- Training of personnel is not included. Training will be organized and executed by UNITAR in concordance with the client.
- Not all medical equipment is listed. Based on request, a complete overview can be provided.
- Individual packages can be worked out. Also, the installation in already existing buildings (e.g. health centers) is possible.
- Pricing will be provided upon request.

Benefits

SPEED	Being a kit of parts, laboratory and clinic are easy to transport and very fast to implement anywhere.
SIMPLICITY	Installation is easily done by small teams.
FLEXIBILITY	Thanks to a modular approach, power and physical space can be added within very short timeframe.
OPEX	Thanks to the integrated solar system and the BOS AG energy storage system, electrical power supply is secured for medical appliances.
CONNECTIVITY	Through the connection to internet through GSM modem or satellite uplink, remote monitoring, training and dissemination of information are possible, as also online consultation.
LONG LASTING SOLUTION	Laboratory and clinic can be used after the end of the Corona crisis, improving general health care for the population.

MADE IN **GERMANY**